


Output Results	
Modeled (85th percentile storm) Rainfall Depth (in)	1.0
Peak Intensity (in/hr)	0.1917
Undeveloped Runoff Coefficient (Cu)	0.1
Developed Runoff Coefficient (Cd)	0.196
Time of Concentration (min)	56.0
Clear Peak Flow Rate (cfs)	0.0496
Burned Peak Flow Rate (cfs)	0.0496
24-Hr Clear Runoff Volume (ac-ft)	0.0214
24-Hr Clear Runoff Volume (cu-ft)	930.7243



LEGEND:

PERMEABLE PAVER DRIVEWAY (17,275 SF)

BUILDING ROOF AREA (6,971 SF)

VEGETATED AREA (30,928 SF)

DECOMPOSED GRANITE/GRAVEL WALKWAYS (2,247 SF)


SWIMMING POOL (547 SF)

----- LIMITS OF WORK

Required Storm Storage Per Unit				
		AREA	Req. Volume (ft ³)	Req. Volume (gal
BLDG 1	l	744	99	743
BLDG 2	2	1278	171	1,277
BLDG 3	3	370	49	370
BLDG 4	1	744	99	743
BLDG 5	5	370	49	370
BLDG 6	5	370	49	370
BLDG 7	7	370	49	370
BLDG 8	3	372	50	372
RESIDE	ENCE	2353	314	2,351
Total		6971	931	6964

FOR THE PURPOSES OF CALCULATING REQUIRED STORAGE VOLUME TO SATISFY LOS ANGELES COUNTY POST CONSTRUCTION RUNOFF PLAN REQUIREMENTS:

- ROOF AREAS WERE CONSIDERED TO BE IMPERVIOUS
- THE PERMEABLE PAVER DRIVEWAY, THE DECOMPOSED GRANITE/GRAVEL WALKWAYS, AND LANDSCAPE AREAS WERE CONSIDERED TO BE PERVIOUS.
- A CISTERN WILL BE BUILT UNDERNEATH EACH BUILDING, AND THE CISTERNS WILL BE SIZED TO CAPTURE A PRORATED AMOUNT OF THE REQUIRED VOLUME, CALCULATED USING HYDROCALC 0.3.1 (SEE LEFT), BASED ON THE ROOF AREA THAT EACH CISTERN WILL BE COLLECTING FROM. THE STORM WATER WILL THEN BE REUSED FOR IRRIGATION PURPOSES. MINIMUM REQUIRED VOLUME FOR EACH BUILDING CAN BE SEEN IN THE TABLE TO THE LEFT.



Reseda Boulevard, Northridge, CA 91326 e: (818) 832-1710·Fax: (818) 832-1740 DER THE SUPERVISION OF: WILLAS WILLAS WILLAS

PROJECT

33528 MULLHOLLAND HWY MALIBU, CA 90265

SHEET TITLE
POST—

CONSTRUCTION RUNOFF PLAN

ISSUE

PHASE

County Submittal Package

SCALE AS SHOWN
ORIGIN DATE
PLOT DATE 02/26/2016

DRAWN BY: CK
CHECKED BY: MW

SHEET

EC-2

2 of 2